Abstract estimate for constructing a Village Elementary School at Manchanahalli, Yedatore Taluk, Mysore Division.

690

Items of work	Per	Quantity
Clearing site and levelling the ground	L. S.	...
Earthwork excavation	C. yd.	36
Burnt brick in clay	C. ft.	3,271
Do chunam	"	268
Burnt stone slabs dressed and fixed	S. ft.	285
Chunam plastering	Sq.	46·00
White and colour washing	"	46·00
Honney wood work wrought and put up	C. ft.	75·14
Roofing with 1st class Mangalore tiles on teak reepers, etc., complete	Sq.	15·25
Mangalore ridge tiles set in mortar and cement pointed	R. ft.	55
Chunam borders at gable end	"	108
Cutting grooves in stone uprights	Each	8
Coping with burnt brick in chunam and plastering	R. ft.	53
Capitals to gate pillars	Each	2
Flooring with gravel including cowdung washing, etc., complete	C. yd.	25
Honney wood battened doors, planks 1½" thick including frames and hinges, etc., complete (4"×3").	S. ft.	98
Honney wood battened windows with 6 iron bars ⅝" dia. etc., complete	"	81
Mangalore ventilating tiles	Each	8
Painting chocolate	Sq.	5·28
Wood oiling 2 coats	"	7·00
Honney wood gate shutters including painting iron works and fittings, etc., complete ...	S. ft.	22
Providing black boards	"	4·9

A. PUTTUSAMAIYA, *Executive Engineer.*

KADUR DIVISION.

Dated 9th February 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 28th February 1919, for constructing Police Lines and Pukka Station at Kalasapur, Chikmagalur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st December 1919.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Police Lines and Pukka Station at Kalasapur, Chikmagalur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of detailed quantities for constructing Pukka Police Station at Kalasapur, Chikmagalur Taluk.

No.	Items of works	Per	Quantity
1	Earthwork excavating, foundation and filling in basement	C. yd.	67
2	Chunam concrete	C. ft.	557
3	Rough stone in clay.	"	1,602
4	Burnt brick in clay	"	1,505
5	Burnt brick in mortar	"	436
6	Burnt stone slabs, 6" thick	S. ft.	238
7	Plastering with mortar	Sq.	39·06
8	Burnt brick in mortar coping	R. ft.	67
9	White and color washing	Sq.	39·06
10	Honneywood work wrought and put up	C. ft.	49·00
11	Roofing with 1st class Mangalore tiles on teak reepers	Sq.	11·20
12	Ridge tiles set in mortar	R. ft.	40
13	Teakwood ceiling plank, ½" thick, including fixing	S. ft.	210
14	Honneywood door battened with necessary iron fittings, etc.	"	83
15	Teakwood door for lock-up with iron bars, etc., as per type design	"	49
16	Honnewood wiudows with iron bars	"	35
17	Honneywood ventilators with expanded metal and ¾" iron bars	"	11
18	Honneywood eave board with pa inting	R. ft.	128
19	Wood oiling to wood work	Sq.	6·00
20	Silicate painting and coated with varnish	"	5·81
21	Tarring wood work	"	3·00
22	Flooring with 1st class Mangalore tiles, 9" square, over 3" concrete bed and cement pointed.	"	3·92
23	Wooden railings of teakwood as per plan	R. ft.	52
24	Teak gate ordinary with shutters, including iron fittings, etc., complete ...	S. ft.	16
25	Flooring with Cudapah slabs, over 3" concrete bed on cement pointing ...	Sq.	1·52
26	Cement pointing	"	4·12
27	Constructing V-shaped drain with cement plastering ...	R. ft.	100
28	Gravelling and consolidating with lead	C. yd.	12
29	Teakwood finials at ends of gables	No.	2
30	Binding walls on roof	R. ft.	48
31	Clearing site and levelling ground	Lump	sum Rs.

Abstract of detailed quantities for constructing Police Lines at Kalasapur, Chikmagalur Taluk.

No.	Items of work	Per	Quantities	
			Single Block	Additional Block
1	Earthwork excavation and filling in basement	C. yd.	36	25
2	Chunam concrete	C. ft.	332	231
3	Stone in clay	"	692	500
4	Burnt brick in clay	"	770	451
5	Burnt brick in mortar	"	176	141
6	Burnt stone slabs	S. ft.	90	89
7	Honney wood wrought and put up	C. ft.	27·11	17·71
8	Roofing with 1st class Mangalore tiles on teak reepers ..	Sq.	5·15	4·01
9	Ridge tiles set in mortar	R. ft.	14	11
10	Chunam plastering	Sq.	22·00	12·38
11	White and color washing	"	22·00	12·38
12	Honney wood doors, battened	S. ft.	88	88
13	Honney wood window, battened	"	9	9
14	Honney wood ventilator	"	4	4
15	Honney wood eave board	R. ft.	129	45
16	Flooring with cement, 4½" thickness and top cement plaster ..	Sq.	2·40	2·40
17	Chocolate painting	"	4·00	2·65
18	Tarring walls and wood work	L. S.	Rs.	Rs.
19	Brick in chunam, coping with chunam-plastering ...	R. ft.	50	34
20	Flooring with gravel including lead ...	C. yd.	2	2
21	Wood oiling	Sq.	2·33	1·50
22	Chunam borders	R. ft.	61	...
23	U-shaped, concrete cement drain, etc., complete ..	"	116	22
24	Providing chimney	Each.	1	...
25	Providing 1½" diameter pipe for drainage water	"	2	2
26	Constructing seats in latrine	L. S.	Rs.	Rs.
27	Teakwood finials	Each.	2	...
28	Teakwood pendants	"	4	.....

K. PONNAPPA,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF AGRICULTURE.

Sealed tenders for the supply of Cattle Feeds required for the Hebbal Dairy as specified in the table below are invited and will be received in the Office of the Deputy Director of Agriculture, Bangalore up to 2 P. M., on 10th March 1919.

2. Each tender should be accompanied by an earnest money of Rs. 100 which will be forfeited to Government if the successful tenderer fails to execute an agreement for the due fulfilment of the contract or to make the deposit specified in para 7.

3. Tenders should state clearly the rate per ton in the case of straw and the rate per maund of 28 lbs. in the case of the oil cake, wheat bran, and cotton seed, and the rate per measuring (Mysore) seer in the case of salt.

4. The articles should be delivered at the Dairy premises in the Hebbal Farm to the charge of the Dairy Inspector on the Farm, who will measure or weigh the articles before giving a receipt as to the quantity received.

5. The articles should be of good quality, fresh and unadulterated; if they are otherwise, they will be rejected by the Dairy Inspector and the tenderer will have to supply fresh articles instead within three days after the unsatisfactory articles were rejected.

6. The articles should be delivered all at one time or in periodical lots as specified in the table below, beginning from the 1st April 1919.

7. The successful tenderer will be required to deposit within one week from the acceptance of his tender a sum of Rs. 500 and also execute an agreement for the due fulfilment of the contract.

8. Payments for the articles will be made by the undersigned on bills presented after the articles have been supplied and countersigned by the Dairy Inspector taking delivery of the articles.

9. Should the contractor fail to comply with any of the abovementioned conditions, his contract will be forthwith cancelled and the amount of his deposit forfeited to Government.